4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Mallur Oorumundinkere, Shikarpur Taluk;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract quantity of establishment for restoring Mallur Oorumundinkere, Shikarpur Taluk.

No.	*Items of work.*	*Per*	*Quantity.*
Bund—			
1.	Earthwork to bund gravelly soil watering and tamping ...	C. yd.	15,487
2.	Turfing	S. yd.	16,142
3.	Grade stones including bed slabs	Each.	28
4.	Index stones	,,	28
5.	B. M. stones	,,	2
6.	Date stone	,,	1
7.	Register No. stone	,,	1
8.	Gauge stone	,,	1
No. 1 Sluice—			
9.	Repairing and providing iron rod, etc.	Lump sum rupees.	
No. 2. Sluice—			
10.	Earthwork cutting bund and filling the same with consolidation.	C. yd.	138
11.	Earthwork excavation	,,	13
12.	Concrete in surki mortar	C. ft.	31
13.	Burnt brick in surki mortar	,,	619
14.	Burnt stone slabs, dressed	S. ft.	112
15.	Plastering with surki mortar	Sq.	520
16.	Fitting cast iron pipes, 6″ diametre, including Railway freight and cart hire from Railway station to site.	R. ft.	45
17.	Fixing wooden plug with iron rods, etc., complete ...	Lump sum rupees.	
18.	Cutting orifice stone guide and top stone ...	,,	,,
Left waste weir 130 feet—			
19.	Earthwork excavation	C. yd.	892
20.	Burnt brick in surki mortar	C. ft.	1,655
21.	Burnt stone slabs dressed and fitted	S. ft.	507
22.	Plastering with surki mortar	Sq.	19·93
23.	Rough stone sugicut work including bed	C. yd.	286
24.	Turfing the slopes of training bank slopes	Sq.	1·50

V. R. NIJAGAL,
Executive Engineer.

CIVIL HOSPITAL, KOLAR GOLD FIELDS.

Abstract Notification.

Notice is hereby given that sealed tenders will be received by the District Medical Officer in charge of Civil Hospital, Kolar Gold Fields, for the supply of diet and other contingent articles required for the use of in-patients of the Civil Hospital and Female Dispensary, Kolar Gold Fields.

For further particulars, please see *Mysore Gazette*, pages 1656 and 1657, dated 7th November 1912.

T. V. KUPPUSAMI MUDALIAR,
District Medical and Sanitary Officer.